Capsule Summary SM-108 Lower Brambley Maddox Vicinity Private

c. 1890-1900

Lower Brambley, constructed c. 1890s, is significant for its association with the Thomas family, the extent and quality of architectural decoration, as well as its well preserved agricultural setting. Overlooking the confluence of the Wicomico and Potomac Rivers, the dwelling is surrounded by 260 acres of cultivated fields of corn and soybean. Located perpendicular to an oak and cedar tree lined dirt drive, the two story, double-pile, side-passage plan dwelling with a two story wing stands prominently in the landscape. The building is clad with rarely used double-run siding that provides the illusion of thinly spaced clapboard. Another interesting feature is the open cornice that features false or "show" rafters. The interior, however, is particularly well appointed. The formal passage features a panelled stair box with an octagonal newel, turned balusters, and scroll sawn brackets. The parlors, connected by a pair of swinging panelled doors, each contain marbleized stone mantles with cross-shaped decorative motifs.

For much of the nineteenth century, Lower Brambley was the home of the Thomas family. Land records reveal that William H. Thomas, a locally prominent politician and farmer, owned the property for much of the early 1800s. In 1866 William died leaving a sizable estate that included Lower Brambley to his wife Eleanor and his children Mary (later Garner), George R., Matilda, and William H. Thomas, Jr. The property was transferred by the William's heirs to Truman Thomas in 1883. According to oral tradition, the original dwelling, an eighteenth century brick mansion, burned to the ground soon after the transaction. Judging from the architectural evidence, namely the stair construction, mantles, framing, and use of wire nails, the present house appears to have been built in the 1890s-1900s. Descendants of the Thomas family owned the property until 1955.

SM-108, Lower Brambley St. Mary's County Maryland Comprehensive State Historic Preservation Data

<u>Historic Context</u> Geographic Organization: Western Shore

Chronologicial/Developmental Period: Industrial-Urban Dominance, 1870-1930

Historic Period Theme: Architecture

Resource Type Category:

Building

Historic Environment: Rural

Historic Function and Use: Residence

Known Design Source: None

Maryland Historical Trust State Historic Sites Inventory HISTORIC PROPERTIES Form

MARYLAND INVENTORY OF

Surve	À	No.	SM-108
Magi	No	٠.	

DOE __yes __no

1. Na	me	(indicate pr	eferred name)		
historic	Lower Bran	nbley (pref.), Bra	ambley		
and/or comm	on				
2. Lo	catio	n			
Lower Bramstreet & num	blev Lane, ber	approx 1 mile S	of the intersection of	Lower Brambley Lane and	Route 238 (Maddox Rd.)
city, town	Maddox		_x_ vicinity of	congressional district	7
state Man	ryland		county	St. Mary's County	TM-29, B-24, P-6
3. Cla	assifi	cation			
Category district X building(structure site object	(s)	ership ublic rivate ooth c Acquisition n process eing considered oot applicable	Status _X occupied unoccupied work in progress Accessible _X yes: restricted _ yes: unrestricted _ no	Present Use agriculture commercial educational entertainment government industrial military	museum park private residence religious scientific transportation other:
4. Ow	ner (of Prope	rty (give names a	nd mailing addresse	s of <u>all</u> owners)
name Nar	ncy D. Wol	fe and Lawrence T	. Wolfe		
street & numb	ber			telephone no	o.: 301-769-2820
city, town	Chaptico		state	and zip code Md 20	621
5. Loc	catio	n of Leg	al Description	on	
courthouse, r	egistry of o	leeds, etc. St. Ma	ry's County Courthouse		liber MRB 369
street & numb	oer				folio 321
city, town	Leonardt	Own		state 1	Maryland
6. Re	pres	entation	in Existing	Historical Surv	eys
title Lower B	Brambley				
date August	, 1970			federalx state	e <u>X</u> countylocal
⊸epository for	r survey re	cords Maryland	l Historical Trust		
city, town	Crownsvi.	lle		state	Maryland
				0.010	

7. Description

Survey No. SM-108

Condition excellent deteriorated good ruins fair unexposed	Check one unaltered altered	Check one X original site moved date of move	
---	-----------------------------	--	--

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

Contributing Resources: 2

Lower Brambley is situated down a dirt road 1.7 miles southwest of the intersection of Notley Hall Road and Maddox Road (Route 238) near Maddox, Maryland. The house, surrounded by cultivated corn and soybean fields, is situated on a 250 acre parcel overlooking the Potomac and Wicomico Rivers. The dwelling is oriented on a northeast/southwest axis and is approached via a dirt road that is on axis with the land side elevation of the house. Several large trees, including a very large willow oak, line the road.

Lower Brambley, constructed c. 1890s, is a two-and-a-half story, three bay, frame dwelling with a side-passage, double-pile plan and a two story gable end service ell. The house is situated on a roughly fired brick foundation and the exterior walls are sheathed with "double-worked" siding (Note: Here "double worked" refers an individual clapboard that features a pair of bullnose moldings in profile.). The current owner, Nancy Wolfe, is preserving the original sheathing beneath vinyl siding. The open cornice is emphasized by purely decorative rafter tails. The roof is sheathed with asphalt shingles and is pierced by two interior end brick chimneys on the main block and a single chimney flue on the two story ell. All of these chimneys have been rebuilt due to significant deterioration. A small frame dairy is located just to the south of the ell.

The primary or northeast (land side) elevation of the main block is pierced by three symmetrically placed bays on the first and second floors. The first floor bays consist of two, two-over-two, double-hung sash windows and a four panel (the upper two panels exhibit rounded tops) door bounded on each side by a sidelight and by a three light transom overhead. All of these bays are shaded by a porch that is supported by four Tuscan columns. The second floor is pierced by three, two-over-two windows. The half story is lit by a pair of gable dormers whose sides are covered with cedar shingles. The original two-over-two windows have been replaced by paired, one light, modern swinging windows. The two story ell juts back from the main block and is pierced on the first and second floor by modern one-over-one windows. These replaced the previous sash that were all six-over-six windows. The ell's open cornice (as well as the cornice of the entire dwelling) features decorative rafter tails while the roof exhibits a single hip on the southeast side.

The southeast elevation of the dwelling features the gable end of the main block and ell. The main block is pierced on the second floor by a two-over-two window that lights the southeast corner room and a centrally placed two-over-two window that lights the half story. The ell is pierced on the first floor by a four panel door that leads to the original kitchen. An original gable roof awning shelters the doorway. The second floor is pierced on the second floor by a one-over-one window.

The southwest (or waterside) elevation of the main block is largely identical to that of the northeast side. The first floor of the main block is pierced by two, two-over-two windows and a four panel door (the top two panels with rounded tops) that is flanked on each side by sidelights with a three light transom over the whole. The second floor features three, two-over-two windows while the half story is lit by two gable dormers. The dormers each feature a set of paired, one light swinging windows. At the juncture of the main block and service ell is a projecting bay. The front of the bay is pierced by a set of paired one-over-one windows. The northwest side is pierced by a modern door.

8.	Significance	Survey No. SM-108

Period prehi 1400- 1500- 1600- 1700- X 1800- 1900-	-1499 archeology-historic -1599 agriculture -1699 _X architecture -1799 art -1899 commerce		Iandscape architectude Iaw Iiterature Indicatory Indica	science sculpture social/ humanitarian theater
Specific	dates	Builder/Architect		
check:	Applicable Criteria: A and/or Applicable Exception:	BCD ABCDI	EFG	
	Level of Significance:	_national _xstate x	local	

Prepare both a summary paragraph of significance and a general statement of history and support.

Lower Brambley, constructed in the last quarter of nineteenth century, is significant for its association with the Thomas family, the extent and quality of architectural decoration, as well as its well preserved agricultural setting. Overlooking the confluence of the Wicomico and Potomac Rivers, the dwelling is surrounded by 260 acres of cultivated fields of corn and soybean. Located perpendicular to an oak and cedar tree lined dirt drive, the two story, double-pile, side-passage plan dwelling with a two story wing stands prominently in the landscape. The building is clad with rarely used double-run siding that provides the illusion of thinly spaced clapboard. Another interesting feature is the open cornice that features false or "show" rafters. The interior, however, is particularly well appointed. The formal passage features a panelled stair box with an octagonal newel, turned balusters, and scroll sawn brackets. The parlors, connected by a pair of swinging panelled doors, each contain marbleized stone mantles with cross-shaped decorative inlays.

For much of the nineteenth century, Lower Brambley was the home of the Thomas family. Land records reveal that William H. Thomas, a locally prominent politician and farmer, owned the property for much of the early 1800s. In 1866, William died leaving a sizable estate that included Lower Brambley to his wife Eleanor and his children Mary (later Garner), George R., Matilda, George, and William H. Thomas, Jr. The property was transferred by William's heirs to Truman Thomas in 1883. According to oral tradition, the original dwelling was an eighteenth century brick mansion, but this earlier structure burned to the ground soon after the transaction. Judging from the architectural evidence, namely the stair construction, mantles, framing, and use of wire nails, the present house appears to have been built c. 1890s. Descendants of the Thomas family owned the property until 1955.

10. Geographi	cal Data			
Acreage of nominated property Quadrangle name Rock Point, UTM References do NOT comp				Quadrangle scale 1: 24 000
Zone Easting No	rthing	B Zone	E Easting	Northing
C		D	J [] . J [] .	
Verbal boundary description a Same as per deed description.	and justification			
List all states and counties fo	r properties over	lapping state or	county bo	undaries code
state	code	county		code
11. Form Prepa	ared By			
name/title Kirk E. Ranzetta	, Historic Sites	Surveyor		
organization St. Mary's County I	ent. of Planning	& Zoning	date Nov	rember 1997
street & number 22740 Washingto			telephone	301-475-4662

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to:

Maryland Historical Trust Shaw House

21 State Circle

Annapolis, Maryland 21401

(301) 269-2438

MARYLAND HISTORICAL TRUST DHCP/DHCD

100 COMMUNITY PLACE CROWNSVILLE, MD 21032-2023

514-7600

SM-108, Lower Brambley St. Mary's County 7.1 Description

The northwest gable end of the main block is pierced on the first and second floor by a single two-over-two window.

The interior of the main block is organized into a side-passage, double-pile plan. The large side passage features four panel doors to the front and rear parlor as well as an open string stair to the second floor. The stair features an octagonal turned newel, turned balusters, scroll sawn brackets and panelling. Each of parlors, connected by a set of two large four panel doors, feature a marble mantle inlaid on the two sides and frieze by crosses. Both parlors also feature baseboards as well as window and door surrounds. The second floor of the main block features a passage that permits entry into three bedrooms. Two of the bedrooms feature wood mantles that exhibit reeding as well as several round knobs on the two sides and frieze. The attic story is entered via the passage through a narrow enclosed stair. The attic is largely unfinished with the kneewalls roughly plastered but the remaining walls left bare to the studs and rafters. The roof features a common rafter framing system. The framing members are circular sawn dimensional lumber and held in place with early wire nails. The rafters rest on a false plate. Each rafter pair corresponds to the floor joists below. They are also joined together by ties that are merely lapped and nailed to the individual rafters. The rafters are joined at the roof peak with a butt joint.

The ell is entered from the waterside parlor on the first floor while there are two entrances from the main block to the second floor of the ell. Overall, the ell's decorative treatments signal its secondary importance. As a service wing, its staircase, window and door treatments, and spatial organization received less decoration. The ell's first floor originally featured three rooms. The room closest to the main block historically served as a chamber, study, and possibly food preparation area. It features a single wood mantle similar to that found in the two upstairs bedrooms of the main block. To the southwest of this chamber is a stair hall that features entrances to the main block, the original kitchen and pantry, the second floor of the ell, and the exterior. The stair in the passage did not receive much decorative attention as it features a square newel and handrail with rounded edges as well as plain square balusters. The original door to the exterior has been removed and replaced by a projecting bay that overlooks the river. The second floor of the ell originally featured a stairhall, two bedrooms, and a bathroom. The bedroom closest to the main block featured a wood mantle similar to those found in the main block. The bedroom furthest from the main block was originally roughly plastered and probably served as the servants' bedroom.

SM-108, Lower Brambley

St. Mary's County 8.1 Significance

Chain-of-Title

(All deeds are located at the Land Records Office, St. Mary's County Courthouse, Leonardtown, Maryland unless otherwise noted.)

Reference: Liber MRB 369, Folio 321 Grantee: Nancy D. and Lawrence T. Wolfe

Grantor: Nancy D. Wolfe-personal representative for the estate of Harold A. Wolfe.

Date: August 3, 1987

Notes: This deed describes the transfer of "Part of Brambly" or "Lower Brambly" consisting of

260 1/2 acres. It also includes the transfer of the 195 15/100 acre tract called "Brambly

Woodland."

Reference: Liber CBG 56, Folio 293

Grantee: Augustus C. F. Wolfe and Harold W. A. Wolfe Grantor: Mercantile-Safe Deposit and Trust Company, trustee

Date: April 27, 1955

Notes: After the death of A. Dana Hodgdon on or before December 14, 1944, the Mercantile company took possession of the property that Hodgdon had taken out a mortgage on. The St. Mary's Circuit Court of Equity (Case # A 510) ordered the sale of the property and it was sold to the Wolfes for \$47,500.

Reference: Liber JFF 6, Folio 395 Grantee: Truman H. Thomas Grantor: Eleanor Thomas, et al

Date: June 1, 1883

Notes: In 1866, William H. Thomas died leaving his property called "Brambley" to his wife Eleanor Thomas and his children Matilda, George, William H., Jr., George R. and Mary Garner. In his will (Liber JTMR 1, Folio 171), William H. Thomas, Sr. stipulated that his brother Dr. James Thomas and his brother-in-law James Mackubin manage his estate. It was soon after the execution of this will that Truman H. Thomas erected the present frame dwelling at "Lower Brambley." William H. Thomas had received the property via the will of his father George Thomas.

Reference: Liber JH 10, Folio 530

Grantee: George Thomas Grantor: Edward I. Heard Date: October 10, 1836

Notes: The deed documents the transfer of Brambly which contains 397 1/2 acres as well as

Llewellens lots.

Reference: Liber JH 9, Folio 480

Grantee: Edward I. Heard Grantor: Joseph Stone Date: June 10, 1836

Notes: This deed notes that Brambly and Llewellen's lots had formerly been owned by "Richard

Jordan (now deceased) and more recently {by} a certain Jeremiah Booth.

S'M -108 LOWER BRAMBLEY Bushwood Private

circa 1875

The house at Lower Brambley on the Wicomico River was built about 1875. It is a frame, clapboard-covered building with a hipped roof, double dormers and a large wing. It was the home of Truman H. Thomas.

Lower Brambley and Upper Brambley, are

part of the land granted to Dr. Thomas Gerard in various

grants beginning in 1639. It is said that Brambley

the hame of

is a corrupted form of "Bromley," Dr. Gerard's estate

in England.

Also see archeological listing S^\prime M -185.

MARYLAND HISTORICAL TRUST WORKSHEET 1901085504

NOMINATION FORM for the

NATIONAL REGISTER OF HISTORIC PLACES, NATIONAL PARKS SERVICE

	Brambley,					
2.	LOCATION					
4	STREET AND NUMBER:					
	CITY OR TOWN:					
	Bushwood					
	STATE			COUNTY:		
	Maryland			St	. Mary's	
3.	CLASSIFICATION					
Sacrit Hill	CATEGORY	T				ACCESSIBLE
	(Check One)		OWNERSHIP		STATUS	TO THE PUBL
	District Building	Public	Public Acquisit	ign:	D 000 1 1	Yes:
	Site Structure	Private	In Pro		Occupied Unaccupied	Restricted
	Object	☐ Both		Considered	Preservation wa	- I
					in pragress	□ No
					in progress	
н	PRESENT USE (Check One or M					
		overnment	Pork		Transpartation	Camments
		dustrial	Private Reside	ence [Other (Specify)	
		litary	Religious	_		
	Entertainment Mu					
Z.M.	OWNER OF PROPERTY		Scientific			
7.5	OWNER OF PROPERTY	Peach Ch				
ON	OWNER OF PROPERTY OWNER'S NAME: Long View B			STATE:		
	OWNER OF PROPERTY OWNER'S NAME: Long VIEW & STREET AND NUMBER: CITY OR TOWN:	Peach Ch		STATE:		
	OWNER OF PROPERTY OWNER'S NAME: Long VIEW B STREET AND NUMBER:	Peach Ch		STATE:		
	OWNER OF PROPERTY OWNER'S NAME: LONG VIEW S STREET AND NUMBER: CITY OR TOWN: LOCATION OF LEGAL DESC. COURTHOUSE, REGISTRY OF D	RIPTION DEEDS, ETC:	S	STATE:		
	OWNER OF PROPERTY OWNER'S NAME: Long VIEW & STREET AND NUMBER: CITY OR TOWN: LOCATION OF LEGAL DESC	RIPTION DEEDS, ETC:	S	STATE:		
	OWNER OF PROPERTY OWNER'S NAME: LONG VIEW S STREET AND NUMBER: CITY OR TOWN: LOCATION OF LEGAL DESC COURTHOUSE, REGISTRY OF D St. Mary's Co STREET AND NUMBER:	RIPTION DEEDS, ETC: OUNTY COURT	house			
	OWNER OF PROPERTY OWNER'S NAME: Long VIEW S STREET AND NUMBER: CITY OR TOWN: LOCATION OF LEGAL DESC. COURTHOUSE, REGISTRY OF D St. Mary's Co	RIPTION DEEDS, ETC: OUNTY COURT	house			
	OWNER OF PROPERTY OWNER'S NAME: LONG VIEW STREET AND NUMBER: CITY OR TOWN: LOCATION OF LEGAL DESC COURTHOUSE, REGISTRY OF D St. Mary's Co STREET AND NUMBER: Washington St	RIPTION DEEDS, ETC: OUNTY COURT	house	rive	ryland	
5.	OWNER OF PROPERTY OWNER'S NAME: Long VIEW S STREET AND NUMBER: CITY OR TOWN: LOCATION OF LEGAL DESC. COURTHOUSE, REGISTRY OF D St. Mary's Co STREET AND NUMBER: Washington St. CITY OR TOWN: Leonardtown	RIPTION DEEDS, ETC: Sunty Court Treet and Co	house ourthouse Dr	rive	ryland	
5.	OWNER OF PROPERTY OWNER'S NAME: Long VIEW S STREET AND NUMBER: CITY OR TOWN: LOCATION OF LEGAL DESC COURTHOUSE, REGISTRY OF D St. Mary's Co STREET AND NUMBER: Washington St CITY OR TOWN: Leonardtown Title Reference of	RIPTION DEEDS. ETC: Sunty Court Treet and Co	house ourthouse Dr	rive	cyland #):	
5.	OWNER OF PROPERTY OWNER'S NAME: Long VIEW S STREET AND NUMBER: CITY OR TOWN: LOCATION OF LEGAL DESC. COURTHOUSE, REGISTRY OF D St. Mary's Co STREET AND NUMBER: Washington St. CITY OR TOWN: Leonardtown	RIPTION DEEDS. ETC: Sunty Court Treet and Co	house ourthouse Dr	rive	ryland #):	
5.	OWNER OF PROPERTY OWNER'S NAME: LONG VIEW S STREET AND NUMBER: CITY OR TOWN: LOCATION OF LEGAL DESC COURTHOUSE, REGISTRY OF D St. Mary's Co STREET AND NUMBER: Washington St CITY OR TOWN: Leonardtown Title Reference C REPRESENTATION IN EXIST TITLE OF SURVEY:	RIPTION DEEDS, ETC: DUNTY COURT OF CURRENT	house ourthouse Dr	rive	. #);	Local
5.	OWNER OF PROPERTY OWNER'S NAME: LONG VIEW S STREET AND NUMBER: CITY OR TOWN: LOCATION OF LEGAL DESC COURTHOUSE, REGISTRY OF D St. Mary's Co STREET AND NUMBER: Washington St CITY OR TOWN: Leonardtown Title Reference C REPRESENTATION IN EXIST TITLE OF SURVEY:	RIPTION DEEDS, ETC: DUNTY COURT OF CURRENT	house ourthouse Dr	rive STATE Man Ok & Pg	. #);	Lacal
5.	OWNER OF PROPERTY OWNER'S NAME: LOCATION OF LEGAL DESC. COURTHOUSE, REGISTRY OF D. St. Mary's Co. STREET AND NUMBER: Washington St. CITY OR TOWN: Leonardtown Title Reference of REPRESENTATION IN EXIST. TITLE OF SURVEY: DATE OF SURVEY: DEPOSITORY FOR SURVEY REG	RIPTION DEEDS, ETC: DUNTY COURT OF CURRENT	house ourthouse Dr	rive STATE Man Ok & Pg	. #);	
5.	OWNER OF PROPERTY OWNER'S NAME: LONG VIEW S STREET AND NUMBER: CITY OR TOWN: LOCATION OF LEGAL DESC COURTHOUSE, REGISTRY OF D St. Mary's Co STREET AND NUMBER: Washington St CITY OR TOWN: Leonardtown Title Reference C REPRESENTATION IN EXIST TITLE OF SURVEY:	RIPTION DEEDS, ETC: DUNTY COURT OF CURRENT	house ourthouse Dr	rive STATE Man Ok & Pg	. #);	Local
5.	OWNER OF PROPERTY OWNER'S NAME: LOCATION OF LEGAL DESC. COURTHOUSE, REGISTRY OF D. St. Mary's Co. STREET AND NUMBER: Washington St. CITY OR TOWN: Leonardtown Title Reference of REPRESENTATION IN EXIST. TITLE OF SURVEY: DATE OF SURVEY: DEPOSITORY FOR SURVEY REG	RIPTION DEEDS, ETC: DUNTY COURT OF CURRENT	house ourthouse Dr	rive STATE Man Ok & Pg	. #);	Local


SEE INSTRUCTIONS

	Excellent	Good Fair	☐ Deteriorot	ed Ruins	Unexposed
CONDITION		(Check One)		(Ch	eck One)
	Altered	☐ Uncite		☐ Moved	Original Site
ESCRIBE THE P	RESENT AND ORIGIN	IAL (if known) PHYSI	CAL APPEARANC	E	

(....

☐ Pre-Calumbian ☐ 15th Century	☐ 16th Century ☐ 17th Century	☐ 18th Century ☐ 19th Century	20th Century
SPECIFIC DATE(S) (If Applicable	le and Known) 1930s		
AREAS OF SIGNIFICANCE (Che Abar iginal Prehistoric Historic Agriculture Architecture Aft Cammerce Communications Canservation	Education Engineering Industry Invention Landscape Architecture Literature Military Music	Palitical Palitical Religian/Philasaphy Science Sculpture Sacial/Humanitarian Theater	Urban Planning Other (Specify)
STATEMENT OF SIGNIFICANCE			
	tan and so the		
	100 and acceptan		
	100 and acceptan		
	100 and acceptan		

		13 * : NA	1300		
	RAPHICAL DATA	THOE COORDINATES	1	LATITUDE AND LO	NGITUOE COORDINATES
		CATING THE PROPERTY	0	OEFINING THE CENTI	ER POINT OF A PROPERTY
ORNER	LATITUOE	LONGITUOE	R	LATITUDE	LONGITUOE
	Degrees Minutes Second	ds Degrees Minutes Second		Degrees Minutes Second	s Degrees Minutes Second
NW		0 ' "		0 , *	0 ,
NE	0 ,	0 , 1			
SE					
APPROXI		OMINATEO PROPERTY:			
	PREPARED BY				
	NO TITLE:				
NAME A	NO TITLE:				OATE
	NO TITLE:				OATE 8-70
ORGANI	NO TITLE:				
ORGANI STREET	NO TITLE: ZATION ANO NUMBER:				
ORGANI	NO TITLE: ZATION ANO NUMBER:			STATE	
ORGANI STREET	ANO NUMBER:				8-70
ORGANI STREET	ANO NUMBER:	fficer Review:		STATE (Office Use Onl	8-70
ORGANI STREET CITY OF	NO TITLE: ZATION ANO NUMBER: R TOWN: te Liaison 0:			Office Use Onl	8-70
ORGANI STREET CITY OF	NO TITLE: ZATION ANO NUMBER: R TOWN: te Liaison 0:	of this prope	rty	Office Use Onl	8-70
ORGANI STREET CITY OF	TOWN: te Liaison O: Significance	of this prope	rty	Office Use Onl	8-70
ORGANI STREET CITY OF	TOWN: te Liaison O: Significance	of this prope	rty	Office Use Onl	8-70






=M-108 Lower Branking KIN FIRST Det 1997



Louis Francis 24 Mary's (really Cork formation 714 177 and SHEAR



-M-108		
Omer Grandley		
t him is comby		
1 1997 1 1997		
Tire de sian looking 1,		
3 of 4		



SM-108 St. hors's County Kick Range #4 214 1117 1.1:11 Martin February S